



# Pipelines as Preferential Pathways: Use of Materials for Construction Which Can Seal or Treat Potential Leaks or Voids



**November 2015**



\* Unique stone-core design



[www.aquablok.com](http://www.aquablok.com)

# Presentation Outline




- Problem Statement – Preferential Pathways
- Introduction to AquaBlok / AquaGate
- Overview of applications
- Summary/Questions/Discussion

We've built a   
**Better Bentonite.**<sup>sm</sup>

# Problem – Preferential Pathways

## PREFERENTIAL PATHWAYS; UNDERGROUND PIPES AND UTILITY LINES CAN BE CONDUITS FOR THE MIGRATION OF CONTAMINANTS

Written by Stephen R. Henshaw, P.G., President & CEO, EnviroForensics  
As seen in the March 2013 issue of Cleaner & Launderer



Typical Pipeline Construction




## Preferential Flow Pathways: Conduits for Groundwater Contamination by Lisa Weatherford

Tuesday, February 18th, 2014

"New research by the U.S. Geological Survey (USGS) concerning the vulnerability of our nation's underground drinking water supplies offers a better understanding of how contamination can occur and what we can do to stop it. Yesterday we reviewed three basic measures for drinking water analysis and today we will look at the importance of preferential flow pathways contribute to groundwater contamination."

# Problem – Preferential Pathways

## Spill Prevention, Control, and Countermeasure (SPCC)



SPCC rules are intended to prevent a discharge of oil into navigable waters or adjoining shorelines.



Pipe Penetrations as Failure Point in Berm/Dike



Low-Permeability Materials for Flood Control

# AquaBlok Technology Platform

Composite Particle Coating Approach:  
A Delivery Method for Uniform Placement of Small  
Quantities of High-Value Materials

- Uniform Distribution
- Flexible/Rapid Installation (Low Cost)
- Custom Blends for Targeted Designs
- Can Vary/Control Permeability
- Placement through Deep Water
- Marine & Freshwater Blends



powder coating

+



aggregate core

=



AquaGate+ “composite particle”



# Low-Permeability for Sealing and Chemical Isolation Barriers

Applied *through* standing water or in the dry



Refinery/PAH Sites



Metals/DDT




PAH / PCBs



MGP Sites



Landfill Cap






# Aquagate<sub>+</sub>

## Permeable Materials for In-Situ Treatment & Remediation Applications



Refinery/PAH Sites



# Adsorptive Material – Petroleum Based Contaminants

Aquagate<sub>+</sub> ORGANOCCLAY™

REMEDICATION TECHNOLOGIES  
Technical Data

CETCO®



**Aggregate:** Nominal AASHTO #8 (1/4-3/8”) or customized to meet project-specific need \* Limestone or non-calcareous substitute, as deemed project-appropriate

**Binder:** Cellulosic polymer

**Permeability:**  $1 \times 10^{-2}$  to  $1 \times 10^{-5}$  cm/sec

**Dry Bulk Density:** 65 – 85 lbs/ft<sup>3</sup>

**Moisture:** 10 – 20% (maximum)

## ORGANOCCLAY® P ORGANIC ADSORPTION MEDIA (POWDER GRADE)

### Product Description:

Organoclay® P is a proprietary powder adsorption media effective in removing oils, greases other non-aqueous phase liquids (NAPL) and other dissolved high molecular weight/low solubility organic contaminants.

### Characteristics:

- Hydrophobic; will not absorb water or swell when wetted
- Non-toxic to marine and benthic organisms
- High adsorption capacity of oils, greases and other NAPL
- Demonstrates noncompetitive sorption—can sorb multiple contaminants

### Properties:


Property	Value	Test Method
Particle Size	70% Min. passing 200 mesh sieve	CETCO Test Method
Bulk Density	50-54 lbs/ft <sup>3</sup>	CETCO Test Method
Oil Adsorption Capacity	0.5 lb/lb Min.	CETCO Test Method
Quaternary Amine Content	25% Min.	CETCO Test Method

# BENTONITE: 101



**Swell + Compaction = Low Permeability**

- Naturally Occurring
- High Swell

powdered bentonite coating



solid aggregate core



sodium bentonite and binder expands when hydrated

# AquaBlok

1 min post  
hydration

time →

# AquaBlok

24 hr post  
hydration



Extreme low-permeability ( $5 \times 10^{-8}$  cm/sec)  
result of consistent swell and self-compaction

# Values & Technical Advantages

- **Offers Targeted Placement** – can be placed *through* or *directly into flowing water* - will not drift or dissipate, minimal dusting
- **Easy to Handle/Install** – like stone aggregate
  - install using standard construction equipment
  - no field blending/mixing required
  - *no mechanical compaction* the material required
- **Durable**
  - Self-healing (even through drying and re-hydration)
  - Compressive strength (due to internal aggregate core)
- **Safety** – no trench boxes needed

Nature's Duct Tape.  
Simple. Unique. Versatile. Effective.



# AquaBlok®

## Examples of Applications: Ponds, Basins & Liner Repair



# Preferential Pathways Formed by Debris in Subsurface







Repair Enhanced with Aggregate  
Cover Over AquaBlok Layer

# AquaBlok®

## Dams, Berms & Levees



## Vertical Barrier Trench Construction


# Application Example



**Fort Smith, AR** – Water Treatment Detention Basin

# Application Example

## Vertical Barrier Trench



not to scale



Post-Repair Water  
Elevation Returned  
to Design Levels

# Application Examples


## Preferential Pathway - Flow Along Pipes



**Anti-Seep Collar – Flowing Water**

# Application Examples

## Pipeline & Utility-related Applications



## Trench Dams/Anti-Seep Collars

# Design/Installation of Anti-Seep Collar

## Elimination of Pipe Bedding as Preferential Pathway





FIGURE 1  
TRENCH DAM (EXAMPLE)

# Installation: Anti-Seep Collar/Berm Stability

Location: West Norriton, Pennsylvania

Setting: Retention/Detention Basin


Right: AquaBlok placement from a bulk bag by excavator – note discharge snout directing product into trench cut perpendicular to the overflow discharge pipe.



Left: Mini excavator used (narrow bucket) to create trench for AquaBlok placement. Right: Completed anti-seep collar around pipe.



# Trench Dam Construction Considerations -



1. **Width of Dam** – 6-inch thickness will provide hydraulic conductivity of approximately  $5 \times 10^{-8}$  in hydrated state.
2. **Bedding Depth / Distance Under Pipes** – Typically recommended to be a minimum of 6-inch.
3. **Trench Width** – Where collars are keyed into surrounding soils, it is recommended that AquaBlok extend a minimum of 1-ft beyond undisturbed material.

# Application Examples

## Preferential Pathway - Flow Along Pipes



**Setting / Purpose:** Pipeline cap and Anti-Seep Collar. Objective was to cut off site contaminant pathways during excavation and installation of natural gas pipeline.




### Installation Notes:

- Cofferdam approach used to isolate pipe trench from surrounding soil
- Continuous measurement of AquaBlok performed to insure design thickness of cap
- AquaBlok placed in lifts with each layer hydrated to insure hydraulic conductivity
- No additional anti-seep collars were placed along pipeline





# Application Examples

## Berms, Banks & Slope Stability



## Cellular Confinement/Slope Protection

# Dike Wall / Berm Repairs – Alternative Construction Approach



**AquaBlok®**  
Composite Particle System

105 WOODLAND AVENUE  
SILANTON, OHIO 43053  
1-419-820-1320  
WWW.AQUABLOK.COM

©2015 AQUABLOK, LTD. ALL RIGHTS RESERVED

## ALTERNATIVE DIKE REPAIR DETAILS

PROJECT NO.: AQB105  
SHEET TITLE DATE: MAY 2015  
CAD DWG FILE: AQB105.100.3020  
PLOT DATE: 5/16/15

# Handling/Installation Factors

## Handling / Installation Advantages:

- Place directly through water column
- Self-compacts on bottom – hydration fills voids to create stable erosion resistant cap layer
- Conventional construction equipment used for placement
- Easy to confirm uniformity of installation (core samples)
- Handles like sand or gravel
- Can be manufactured on-site for significant cost savings





**AquaBlok**<sup>®</sup>  
Composite Particle System

better Bentonite